

## Portion of Map 069, Parcel 29.02, Central Point Road HIGH INTENSITY SOILS MAP FOR Civil District 07, Grainger County, TN CONVENTIONAL DRAINFIELD SYSTEMS


Project: # xxxxx^ For: Kathleen Aillion Harvey Morgan Road





SLOPE CLASS SOIL NAME **SOILS LEGEND** 


**DEPTHS** 



## HIGH INTENSITY SOILS MAP BY:

Michael J. Searcy No.0025 Tennessee Licensed Professional Soil Scientist

Dandridge, Tennessee 37725 etsoilguy57@gmail.com 351 Cline Rd. Apprentice Elizabeth Wagar Assisting (865) 850-5499



Vicinity Map



60 MPI 45 MPI 45 MPI 30 MPI >48" >48" >48" >48" due to position in the of the year. The unit is considered well drained and karst, percable. cherty limestone. Subsoils are clayey, but well structured with numerous angular chert exists at depths between 24 and 36 inches. Any fieldline installation made within the derived residual soils Minvale soils have formed in deep colluvium from cherty limestone residual sources located higher in the local landscape. These soils are suitable for fieldline use, but pinnacle rock is not unknown at more shallow depths. The unit is karst, percable with fragments. Depth to limestone bedrock is greater than 60 inches here, although Soils of the Fullerton soil series have formed in deeply weathered residuum from protection is required higher in the watershed and dominated by limestone residual soils. Surface water unit must have surface water protection to prevent over-saturation during wet periods are as dry as possible to prevent glazing trench walls. no restrictions. It is recommended that fieldline installations be made when conditions Etowah soils are a product of deep alluvial deposits washed from landscapes located Soils of the Emory series have formed in deep alluvium and colluvium from limestone here to prevent over-saturation during wet periods of the year landscape. The unit is considered karst, percable. located higher in the landscape. An ancient buried surface layer Red/ Green Red/ Green Green Red/ Green

Fullerton, 0-30%

0-48"

Minvale, 0-15%

0-48"

surface water protection is required to prevent over-saturation during wet periods of

the year. The unit is considered karst, percable.

Etowah, 0-15%

0-48"

Emory, 0-15%

0-48"

Cut/Filled/Compacted

Disturbed,

 $\frac{1}{8}$ 

NOT RATED

NOT RATED (INCHES) LAYERS

within these delineations that are suitable for fieldline installations. A Special evaluated for fieldline installations. A Special Investigation of Soils may reveal areas

These areas have been disturbed (cut, filled or compacted) and have not been

Red

investigation is beyond the scope of this mapping.

RATE (MPI)

## IF THESE SOILS ARE DISTURBED (CUT, FILLED OR COMPACTED) AFTER THE DATE SHOWN BELOW, THIS SOILS MAP WILL NOT BE VALID!

l Michael J. Searcy, affirm that this soil map paets the standards establishednin the Regulations to Govern Subsurface Sewage Disposal, The Soils Handbook and Soil Taxopomy. No offier warranti ok and Soil Taxopomy. No other warranties are

Signature of Soils Consultant does not constitute approval of lot by The Division of Groundwater Resources.

cut bank drive control flag ♂A1 fence culvert <sub>12</sub> doline bottom rock outcrop Vv gully (15' setbacks) ... drain (15' setbacks) drain (25' setbacks) — · Map Legend

power pole 👂 iron pin found ipf perc hole 👴

8/28/2022